

PROJECT :-

MAS CATERING BUILDING IN KUALA LUMPUR INTERNATIONAL AIRPORT

LOCATION :-

KLIA, Sepang

CLIENT :-

MAS

PROJECT COST :-

RM 320 Million

COMPLETION DATE :-

1997

Job Description :-

The Catering building was the largest kitchen cum office for the production of inflight meals in Malaysia serving MAS and most International Airlines flying to and from Malaysia. It was estimated that an average 35,000+ meals could be produced per day at its full operation.

The building was an "L" shaped reinforced concrete structure, The long leg measured 128m x 136m and the shorter leg, 68m x 56m. The heights vary from 1-storey at the plant room to 5-storey at the Penthouse. The walls were double layered made of brick walls clad with preformed insulated panels and the roof covered with metal roofing sheets. There building housed kitchens, cold storages, ware washer and etc. There were 3 service tunnels running below the ground floor. Other structures associated to it were the 12.5m high r.c. water tank, the Bin Store & High Bay Pallet Stores.

SERVICES PROVIDED :-

Structural design of the building, equipment supports and design coordination for the installation of kitchen equipment, power and free system and various works discipline. QA/QC support during the construction.



Mas Catering Building in KLIA