

**PROJECT :-****Kuala Lumpur Convention Centre****LOCATION :-**

Kuala Lumpur City Centre (KLCC)

**PROJECT COST :-**

RM 550 Million

**CLIENT :-**

Sunway Construction Berhad

**COMPLETION DATE :-**

May 2005

**Job Description :-**

The Project comprises design and construction of the proposed Convention and Exhibition Centre at KLCC.

**The Details Works include :-**

- Pile foundation using combination of 800mm dia. to 1500mm dia. bored piles and raft foundation.
- Two levels of diaphragm wall basement with combination of precast hollow core slab, prestressing slab / beam and conventional r.c. floor system.
- 5 storey superstructure comprising mainly steel columns, steel floor beams and metal decking slab including 30 m span steel trusses with precast half slab floor structure and 50 m span Plenary Hall floor structure comprises mainly of steel trusses.
- Supporting utilities and C&S infrastructure required for operation of the above facilities.

**SERVICES PROVIDED :-**

- Preparation of Detailed Design
- Construction Supervision



Kuala Lumpur Convention and Exhibition Centre