

PROJECT :-

POLIS HEADQUARTERS BUILDING

LOCATION :-

Kuala Lumpur

CLIENT :-

Jabatan Kerja Raya

PROJECT COST :-

RM 60 Million

COMPLETION DATE :-

1984

Job Description :-

The Police Headquarters building consists of a 33-storey Tower and adjacent 5-storey Podium Block. The total built-up is 54,000sq. m and is supported by bored pile with diameter ranging from 1220mm to 1524mm. The technique features conventional cast-in-situ reinforced concrete construction and slip forming of corewalls

The Details Works include :-

- Detailed design of bored pile foundation from 1220mm to 1524mm diameter
- Detailed design of the 33-storey tower blocks and 5-storey podium block

SERVICES PROVIDED :-

- Preparation of Detailed Design
- Construction Supervision and Contract Administration



Polis Headquarters, Kuala Lumpur