

PROJECT :-

APMC, KANTHAN KK3 (2000 TPD) MODERNISATION WORKS, PERAK

LOCATION :-

Ipoh, Perak

CLIENT :-

Associated Pan Malaysia Cement Sdn Bhd

PROJECT COST :-

RM 62 Million

(including various up-rating works)

COMPLETION DATE :-

1984

Job Description :-

The works include site development, limestone crusher, clay intake and crusher limestone clay store, raw material feed bins, limestone and clay feed bins, clay drying plant, railway coal intake, coal store, coal grinding plant, clay dryer, material transport, raw meal grinding plant, raw meal silo, homogenizing silo, weighing station, preheater, motor and fan foundation, rotary kiln piers, clinker cooler, gravel bed filter, 30,000 MT clinker silo, 1,500 MT auxiliary clinker steel silo, chimney, electrostatic precipitator, cooling water system, clinker grinding plant, roller press, water treatment plant, control room, cable bridge, 66 kV main and distribution substations, etc.

Summary :-

Piling : 2,800 points
Reinforced Concrete : 33,000 cu.m
Structural Steel : 6,500 tonnes

SERVICES PROVIDED :-

Soil Investigation, topographic survey, site preparation, detailed engineering design for civil and structural works, quantity survey, contract documentation, tender evaluation, contract administration, construction supervision, M&E building services.



APMC, Kanthan KK3 (2000 TPD) Modernisation Works, Perak