

PROJECT :-**KOTA KINABALU DRAINAGE IMPROVEMENT WORKS, BASIN II, SABAH****LOCATION :-**

Kota Kinabalu, Sabah

CLIENT :-

Jabatan Kerja Raya, Sabah

PROJECT COST :-

RM 25 Million

COMPLETION DATE :-

1992

Job Description :-

The Project involved investigating 221 hectares of urban lands affected by poor drainage and flash flooding. The scope called for existing drainage system to be examined and remedial actions formulated to overcome shortfalls. Rehabilitation proposals arising from the investigation included repairs of damaged drains, upgrading on undersize channels and construction of additional drains to improve effectiveness of the drainage network

SERVICES PROVIDED :-

- Geotechnical investigation & survey
- Conceptualizing improvements necessary to existing drainage layout
- Hydrology and Hydraulics studies, using computer modeling techniques
- Preparing of construction drawings and contract documents
- Preparing Engineer's estimate of project costs
- Contract supervision, commissioning & hand-over to Client

**RC Drain under Construction****Piling Works along Drain Alignment****Triple Cell Culvert at Drain Junction**